# IWCD, the Intermediate Water Cherenkov Detector for HyperK

Pablo @ 2<sup>nd</sup> HK-ES meeting (IFAE) -- 2024/09/30





The IWCD is a new 600-ton (300 ton inner volume) intermediate detector for the HyperK project located ~850 m downstream of the J-PARC neutrino source

 $\rightarrow$  the main goal is to make measurements to control systematic errors for the long baseline (and atm) program

IWCD has unique capability to move vertically to probe different off-axis angles and thus neutrino energy spectra to study energy reconstruction, flux characterization and cross sections. Same target as HK-FD.

IWCD will precisely measure the neutrino-nucleus cross section ratios with the most impact in the LBL analysis

$$rac{\sigma_{_{m v_e}}(E_{_{m v}})}{\sigma_{_{m v_\mu}}(E_{_{m v}})}, \, rac{\sigma_{_{m \overline v_e}}(E_{_{m \overline v}})}{\sigma_{_{m \overline v_\mu}}(E_{_{m \overline v}})}$$







## The IWCD Design

IWCD is a simplified water-Cherenkov detector in the sense that it needs to be as buoyant (light) as possible. It will float in a floaded pit moving vertically according to the surrounding water level

A lot of work has been going on in the last year to optimize and make a feasible design:

- Inner volume (ID): 7 m in diameter and 8 m in height
- Pit diameter will be 10.2 m
- To minimum off-axis angle of no more than 1.7°

Instrumented with 370 mPMTs in the ID, of which 100 are those ready for WCTE

The outer detector (OD) design is similar to Hyper-K OD with 3-inch PMT and wavelength shiPing plates (~370 for IWCD)

Tyvek sheets will separate ID from OD, and a geomembrane detector from the pit

Most of the instrumentation (electronics, calibration, etc.) will be installed on top of the detector and move with it



12-gon stainless steel structure frame on which supermodules (SM) with ID mPMTs and OD PMTs are installed

- 3x2 and 2x2 SMs for the barrel
- Larger SMs for the end caps





Sparser and lighter outer structure surrounding the PMT structure on which the geomembrane is attached and which defines the OD

Vertical rails and a floating system on top allow and guide the vertical movement





### Water system

- Reverse osmosis system at ground level for initial filling
- Recirculation system located on top of the detector to maintain water quality
- Ion exchange resins, filter and UV organic removal
- Water system for the pit is also necessary, but much simpler



## Calibration

- Deployed through the CDS:
  - Radioactive sources (Ni-Cf, Am-Be)
  - Xe lamp + diffusser ball
- Lights and cameras for photogrammetry
- Light injectors at different locations of the detector



## Assembly

After Facility Tent Building Complete

Surface Work

1)Assemble bottom frame with membrane & OD Tyvek, pillars and bottom sparse frame (10 days)

2)Install vertical frame with moving system, barrel outer OD Tyvek and membrane, top frame and lifting jig (1 month + 8 days)





3)Crane into pit and attach to guide rails and hang by lifting jig (3 days)

Total: 2 months





				July 2024 Jan. 2025 July 2025 Jan. 2026 July 2026 Jan. 2027 July 2027	1/2028
Name 👻	Duration 👻	Start -	A N	1 J J A S O N D J F M A M J J A S O N D J F M A M J J A S O N D J F M A M J J A S O N D J F M A M J S	JASONDJF
IWCD Site/Facility	1193days? Sat 4/1/23		$\diamond$	🛛 🗴 🔊 Pit construction (19 months)	Tent 🔷
IWCD Detector	1320days	? Tue 1/3/23		Q2 Q3 Q4 Q4   Ase Add Agg Seg Q4 Ber	
Moving System	1082days	? Thu 2/2/23	>		~Proposed
Outer Membrane	714days	Mon 4/1/24	>		IWCD
Support Structures	1083days	Sat 4/1/23			Completion
4 Design and Procurement	1028days	Sat 4/1/23			
Basic Design	328days	Sat 4/1/23	Moc	kup design (by end of June)	
Initial design for facility input	Odays	Mon 9/4/23	2		
Prototype (Mockup) Structure	305days	Tue 7/2/24	Ìģ	parallel to engineering design	to
Prototype Design Review	22days	Tue 7/2/24	1 4	Mockup design review (1 month)	
Complete Prototype design for company consultation	Odays	Wed 7/31/24		Verily ideas and procedures	
Prototype design iteration with com	44days	Thu 8/1/24		Design iteration with company (2 months)	
Start prototype procurement	0days	Tue 10/1/24		10/1	
Prototype procurement and assemb	66days	Wed 10/2/24		Procurement and assembly of mockup (3 months)	
Prototype tests	173days	Thu 1/2/25		Tests with mockup structure	
Full Structure	656days	Sun 9/1/24			
Funding Request	0days	Sun 9/1/24		- Funding request (in e.g. Japan; need more contributions!)	
Funding Review	152days	Mon 9/2/24			
Funding Available	Odays	Tue 4/1/25		4/1	
Detailed Design	260days	Thu 1/2/25		Detector structure	
Detailed Design Review	88days	Fri 10/31/25		Detailed design (14 months)	
Start Support Structures Procureme	Odays	Mon 3/2/26			
Inner Support Structure Procuremer	264days	Tue 3/3/26			
Deliver SM Structures	0days	Thu 3/4/27		Likely need to start procuring earlier	
Outer structure procurement	264days	Tue 3/3/26		(EV202E) depending on budget profile	
Deliver Outer structure	Odays	Thu 3/4/27			
Assembly of outer structure	40days	Mon 3/22/27		Detector structure assembly	
Installation of outer structure	3days	Tue 5/18/27			
Water Systems	1320days? Tue 1/3/23		>		
All-Systems Reviews	370days	Wed 10/2/24			
All-Systems Review 1	66days	Wed 10/2/24			
All-Systems Review 2	66days	Mon 12/1/25		Canada mPMT chinmonto	
WCD Integration	334days	Mon 11/2/26		Assembly Site Prep $\diamond$	

### Importance of IWCD physics measurements

#### **CP** violation

The e over  $\mu$ , neutrino antineutrino double ratio is one of the most limiting uncertainties in the sensitivity of HK to CPV

Currently the uncertainty on this quantity is estimated from theory, of 4.9%.

IWCD can constrain this uncertainty to 3.6% (preliminary)



This measurement largely relies on IWCD's capability to reconstruct pure samples of electron (anti)neutrinos

→ Intrinsic electron-like background

 $\mathcal{V}$ 

 $\mathcal{V}$ 



#### Energy deposited in OD from interactions outside the detector



## Importance of IWCD physics measurements

### Feed-down and true neutrino energy

The energy scale of HK-FD is determined through calibration and the reconstructed energy inferred from CCQE kinematics

However reconstruction and intrinsic neutrino interaction processes (non-QE) tend to make the reconstructed energy of a neutrino lower than its true energy (feed-down)

A similar effect is seen due to the uncertainty in the direction of the beam and its relation with the neutrino spectrum

This alters and diffuses the shape of oscillation probabilities loosing sensitivity about the oscillation parameters



### Importance of IWCD physics measurements

 $\rightarrow$  Impact on CPV and  $\theta_{23}$ 



### Summary

- Challenging detector R&D profitting from WCTE and past WC detectors
- Very limited resources and tight schedule but important for the CP-discovery focused HK program
- Capable of significantly reducing sensitivity-dragging systematic uncertainties in LBL
- Other gains not treated here:
  - Improved BSM searches (e.g. steriles, neutrino decay) by combining ND280 and IWCD data
  - Reducing systematics for sub-GeV atmospheric neutrinos and, to a lesser extent, proton decay
  - Neutrino beam flux characterization
  - ND280 IWCD cross-validation (e.g.  $\sigma_v(O)/\sigma_v(C)$ )