



中国科学院高能物理研究所

Institute of High Energy Physics, Chinese Academy of Sciences

# IHEP plasma accelerator test facility development status

Dr. Dazhang Li  
Institute of High Energy Physics  
On behalf of on IHEP-THU-BNU Team



# Outlines

- **Motivation**
- **PBA TF based on BEPCII linac**
- **Proposed experiments in the near future**
- **Summaries and prospects**



# Plasma Based Acceleration (PBA): $> 1000 E_{acc}$ .

RF cavity:  $< 100 \text{ MeV/m}$




Table-top X/γ sources



High Energy colliders

HEDP platforms

SACLA, 750 m, 8 GeV




LBNL, 20 cm, 7.8 GeV



Affiliations/institutes on PWFA Study




# CEPC Plasma Injector (CPI)



10 GeV e-/e+ beam in a 100 km ring

- Minimum magnetic field = 28 Gs
- Field error  $< 28 \text{ Gs} \times 0.1\% = 0.028 \text{ Gs}$
- Field reproducibility  $< 29 \text{ Gs} \times 0.05\% = 0.014 \text{ Gs}$
- The Earth field  $\sim 0.2\text{-}0.5 \text{ Gs}$ , the remnant field of silicon steel lamination  $\sim 4\text{-}6 \text{ Gs}$ .



10 GeV  
Linac



100 km  
Booster




Collider  
Rings

10 GeV linac + CT coil magnet, or 30 GeV linac + iron-core magnet ? Both lead to significant cost rise  $\sim 1 \text{ B RMB}$






# IHEP-THU-BNU Collaborated team on CPI (since 2017)



**Proposed by Prof. Gao and Prof. Lu on 2017.01**  
**First collaborated group meeting on 2017. 03**  
**Till now, 20+ staffs, 5 postdocs, 20+ PhD students**



# CPI design V3.0 and key issues for CPI



## Key issues for conventional accelerator:

- ① High charge longitudinal shaped bunch;
- ② High current beams combination;
- ③ Low emittance  $e^+$  beamline
- ④ Final focus system design and optimization

## Key issues for plasma wakefield accelerator:

- ⑤ High TR  $e^-$  PWFA and hosing instability;
- ⑥ High repetition rate stable plasma sources
- ⑦ High quality and high efficiency  $e^+$  PWFA
- ⑧ Staging / Cascaded acceleration



## Progress on key issues of CIP

Key issues		Preliminary study/ Conceptual design	Detailed and convincing simulations / designs	Experiment test / Prototype
e- PWFA	HTR	✓	✓	×
	Beam quality preservation	✓	✓	×
	Error analysis	✓	×	×

**Biggest uncertainty: lack of experimental test**

**Need a dedicated PWFA test facility for CPI!**

Conv. acc. physics and techniques	Beam merging	✓	×	×
	Instrumentation	✓	×	×
	Timing synchronization	✓	×	×
	Positron beamline	✓	✓	×
Plasmas source and beam manipulation	Plasma dechirper	✓	✓	✓
	Plasma lens	×	×	×
	Plasma sources	✓	✓	×
	Staging	✓	×	×



# Outlines

- Motivation
- **PBA TF based on BEPCII linac**
- **Proposed Experiments in the near future**
- **Summaries and prospects**






## Hall #10 @ IHEP was used for detector calibration





## PBA TF proposal based on BEPCII linac

- From 2023.09 to 2025.06 (2025.10)
- Unique TF for e<sup>+</sup> and cascaded PWFA









# Detailed beamline design & key issues could be addressed


- ① L-band e- Gun ( $> 5$  nC):  $\sim$  CPI requirement
- ② Beams combination: similar to CPI
- ③ High quality  $e^+$  beam: NO
- ④ Final Focus: even harder than CPI



- ⑤ HTR e- acc.: easier than CPI ( $\sim$ CPI @ SXFEL)
- ⑥ High rep. rate plasma source:  $>$  CPI
- ⑦  $e^+$  PWFA acc.: 1<sup>st</sup> exp. result,  $<$  CPI
- ⑧ Cascaded/staging: 1<sup>st</sup> exp. result,  $<$  CPI



# Timetable and the overall information



- 36 m × 14 m, 2 floors, 1524.97 m<sup>2</sup> in all;
- 50 cm concrete wall between beamline tunnel and laser room;
- 50 cm concrete ceiling on the beamline tunnel,  $\geq 1.5 \text{ T / m}^2$ ;
- 15 cm concrete ceiling on the laser room,  $\geq 0.6 \text{ T / m}^2$ ;
- 4.05 m height @ beamline tunnel & 3 m height @ laser room;

- Replace the electric double girder crane (10 t → 5 t);
- Extend the total power supply to 2000 KVA;
- Cooling water system and AC system are also enhanced;
- The total budget: **~ 10m RMB**
- **MUST** install the beamline in BEPCII tunnel during 2024.07-2024.10





## PBA TF progress ---- clear the lab (2023.11-2024.03)



More than 1400 concrete blocks





## PBA TF progress ---- re-construction (2024.05-2024.09)








## PBA TF progress ---- replace the double girder crane







## PBA TF progress ---- beamline installation in B2 tunnel







## PBA TF progress ---- utility renovation (since 2024.11)







## PBA TF progress ---- utility renovation (2024.11-2025.06)







# PBA TF progress ---- utility renovation (2024.11-2025.06)







## PBA TF progress ---- utility renovation (2024.11-2025.06)










## PBA TF progress ---- utility renovation (2024.11-2025.06)








# PBA TF progress ---- equipment manufacture



光阴极材料Load-Lock装置



光阴极Suitcase




真空法兰试验件检漏


充气法兰  
气密性试验



正在开展的半精加工



L波段  
微波传输系统



S波段  
微波传输系统






# Outlines

- Motivation
- PBA TF based on BEPCII linac
- **Proposed Experiments in the near future**
- **Summaries and prospects**





# Light path design of the PBA TF and beam quality @ IPs




Parameters	Unit	BL-I e- (AM3)	BL-I e- (IP1)	BL-I e+ (AM3)	BL-I e+ (IP1)	BL-I e- (IP1, block)	BL-I e+ (IP1, block)	BL-II e- (IP2)	BL-II e- (IP1)
Energy	GeV	2	2	2	2	2	2	0.15	0.15
Charge	pC	2000	2000	100	100	9.4	0.2	5000	1000
bunch length	ps	10	1	10	1	~1	~1	0.7	1
Geo. emittance	mm·mrad	0.1/0.1	0.1/0.1	0.4/0.4	0.4/0.4	0.011/0.005	0.04/0.02		
RMS beam size	μm	-	150/150	-	300/300	30/40	54/76	35/22	100/50






# PBA experiment proposals — LWFA e- external injection





**PW Laser + BL2 e- (9.45 pC)**

$E \sim 16.6 \text{ GeV}$ , rms energy spread  $\sim 7.7\%$





# PBA experiment proposals — cascaded acceleration



## Stage 1: PWFA @ IP2

L-band e- gun generate 2 bunches  
 Trailer is accelerated from 150 MeV to 170MeV


## Stage 2: PWFA @ IP1

Use 2 GeV e- bunch from BEPCII linac as driver  
 Trailer is accelerated from 170 MeV to 310 MeV




# PBA experiment proposals — PWFA e<sup>+</sup> acceleration


hollow channel plasma



finite-width channel



uniform plasma





**Use BL2 e<sup>-</sup> as driver, and e<sup>+</sup> from BL1 as trailer**  
**Try different schemes for better capture efficiency and beam quality**







# PBA experiment proposals — LWFA e+ external injection

➤ PW laser + BL1 e+



Laser: 18J,  $a_0=2.4$ ,  $w_0=60\mu\text{m}$ ,  $\tau=25\text{fs}$   
 e+: 50pC, 2GeV,  $\sigma_r = 40\mu\text{m}$ ,  $\sigma_z \sim 1\text{ps}$   
 Plasma:  $\sim 1\text{e}17\text{cm}^{-3}$

**Both e+ energy gain > 1GeV**



Laser: 19J,  $a_0=1.1$ ,  $w_0=75\mu\text{m}$ ,  $\tau=30\text{fs}$   
 e+: 7.5 pC, 2GeV,  $\sigma_r = 40\mu\text{m}$ ,  $\sigma_z \sim 1\text{ps}$   
 Plasma:  $\sim 5\text{e}16+2\text{e}16 \times (r(\mu\text{m})/75)^2$



# Outlines

- Motivation
- PBA TF based on BEPCII linac
- Proposed Experiments in the near future
- **Summaries and prospects**





## IHEP PBA study is advancing to a new stage

- Conceptual design of CPI has been carried out since 2017
- The PBA TF based on BEPCII will be ready for commissioning in several months
- The new TF is NOT only for PBA, but also for conventional accelerator R&D
- The new TF is NOT only for CPI, but also for a real plasma-based accelerators
- HOPE to address mainly technical concerns of CPI

- ① **L-band e- Gun (> 5 nC): ~ CPI requirement**
- ② **Beams combination: similar to CPI**
- ③ **High quality e+ beam: NO**
- ④ **Final Focus: even harder than CPI**

- ⑤ **HTR e- acc.: easier than CPI (~CPI @ SXFEL)**
- ⑥ **High rep. rate plasma source: > CPI**
- ⑦ **e+ PWFA acc.: 1<sup>st</sup> exp. result, < CPI**
- ⑧ **Cascaded/staging: 1<sup>st</sup> exp. result, < CPI**

**Thank you and welcome to IHEP**

